

BHAKRA BEAS MANAGEMENT BOARD

CORRIGENDUM No-01

It is hereby notified that the opening date of NIT No 01/2017-18/400 KV T/L DKT Dated 13.10.2017 for R&R of control room, battery room, subordinate rest house and subordinate club building at 400 KV T/L Sub Stn , BBMB, Panipat is hereby extended as under:-

1	Last date of issue of Tender Documents	27.11.2017 Upto 05.00 PM
2	Due date/ Time for submission of Tenders	28.11.2017 Upto 01.00 PM
3	Date/ Time of opening of Tenders	28.11.2017 At 03-30 PM
4	Value of work	8.76 Lacs
5	Earnest Money Deposit	8800/-

In case due date for the receipt/opening of the tender happen to be a holiday, the tenders will be received/opened on next working day.

For more details and revised contents of work login to BBMB official Website www.bbmb.gov.in

(Er. Ravinder Sheokand)
Addl Superintending Engineer
400 KV T/L Division, BBMB
Dhulkote, Ambala City.

CONTENTS OF WORK

Sr. No	Estimate/Contents	Qty.
1	Scraping:- (a) White wash and colour wash	352.23 Sqm
2	Preparation of concrete or plastered surfaces for painting or oil-bound distemper including sand papering the surface applying one coat of linseed oil and filling with approved quality filler, consisting of white lead, linseed oil varnish and chalk mitti including finishing the surface to the required finish complete.	668.60 Sqm
3	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade (02 coats).	2049.18 Sqm
4	Finishing walls with Premium Acrylic smooth exterior paint with silicon additives of required shades with 02 coats applied @ 1.43 Ltr. per 10 sqm over and including base coat of water proofing Cement Paint applied @ 2.20 per KG./ 10 sqm.	1043.62 Sqm
5	Distemping with Acrylic washable oil bound distemper (of approved manufacture) 02 coats over one priming coat to give an even shade.	1361.0 Sqm
6	Preparation of Plastered Surfaces for distemping including surface, applying filling with approved quality filler consisting of Plaster of Paris and chalk mitti including finishing the surface to the required finish complete.	465.0 Sqm
7	Painting two coats excluding priming coat with synthetic enamel paint in all shades on wood work, metallic or plastered, concrete surface to give an even shade. a) With special quality paint	75.0 Sqm
8	Spirit polishing two coats including a coat of wood filler on wood work.	280.0 Sqm
9	Removing old paint with Caustic Soda solution and preparing surface.	280.0 Sqm
10	Scraping:- C) Cement plaster.	896.39 Sqm
11	12.5 mm thick cement plaster 1:4	364.44 Sqm
12	Cement rendering on plaster 1mm thick	225.09 Sqm
13	Extra for providing and mixing water proofing material (liquid or powder) in cement plaster work as per manufacturer guide line and to the entire satisfaction of Engineer-in-Charge.	27.0 Bags
14	16mm thick cement plaster 1:4 in two coat work	627.44 Sqm
15	Cement rendering on plaster 1mm thick	627.44 Sqm
16	Floating coat of 1.5mm thick neat cement laid in one operation to the topping.	1174.91 Sqm
17	Dismantling Concrete or Precast Concrete. d) Cement concrete plain 1:2:4	2.12 Cum.
18	Centring and shuttering for flat surfaces such as suspended floors, roofs, landings, chhajas, shelves etc.	84.35 Sqm
19	Cold twisted deformed (ribbed / tor-steel) Bars Fe-415 grade as per IS-1786-1985 for RCC works, where not included in the complete rate of RCC including bending, binding and placing in position complete.	1.90 Qtl.
20	Reinforced cement concrete M-20 with cement @ 375/KG per cum hand mixed but excluding steel reinforcement centring and shuttering in super	2.12 Cum.

	structure.	
21	Plastering on underside of ceiling 10mm thick cement plaster 1:4.	27.87 Sqm
22	Cutting Chase in brick walls in cement or in floor for embedding G.I. or C.I. pipes lines and making good the same to its Original condition.	61.0 RM
23	Providing, stringing out PVC Pipes as per IS-4985 casting along the Trenches and laying the same in Trenches to correct alignment and gradients, cutting, jointing and testing including cost of specials complete as per specifications. iv) 110mm O/D Pipe of 10Kgf./sqcm.	44.0 RM
24	Providing and fixing Aluminium cover, box cover on coil & wire of split AC in control room. Complete in all respect.	7 Nos.
25	Removing old paint with caustic soda solution and preparing surface.	225.24 Sqm
26	Painting with acid proof paint of approved brand and manufacture to give an even shade two coats.	225.24 Sqm
27	Carriage of material (0.5 to 1.0KM)	11.69 Cum.
	Loading & Unloading	11.69 Cum
28	1 No. Majdoor for dismantling of old PVC Tiles floor & cleaning of surface	153.64 Sqm
29	Providing and laying resilient Vinyl sheet floor covering 2mm thick, having a vinyl plastic wear layer with backing intended for use in light commercial and residential buildings, duly fixed to the base floor using adhesive as approved by the manufacturer.	153.64 Sqm

(Er. Ravinder Sheokand)
Addl Superintending Engineer
400 KV T/L Division, BBMB
Dhulkote, Ambala City.

भाखडा ब्यास प्रबंध बोर्ड

शुद्धिकरण संख्या -01

सभी संबन्धित को सूचित किया जाता है की निविदा न. 01/2017-18/400 KV T/L DKT दिनांक 13.10.2017 जो कि 400 के वी सब स्टेशन बीबीएमबी पानीपत स्थित नियंत्रण कक्ष, बैटरी कक्ष, अधीनस्थ क्लब इमारत एवं अधीनस्थ विश्राम गृह के नवीनीकरण/ मुरम्मत व बदलाव हेतु थी, अब इसकी खुलने की तिथि निम्न अनुसार बढ़ाई जाती है :-

1	टेंडर जारी करने की अंतिम तिथि	27.11.2017 सांय 5 बजे तक
2	टेंडर देने की निश्चित तिथि व समय	28.11.2017 दोपहर 1 बजे तक
3	टेंडर देने की खुलने की तिथि व समय	28.11.2017 दोपहर 3.30 बजे
4	कार्य की कीमत	8.76 लाख
5	धरोहर राशि	8800/-

यदि किसी कारण से टेंडर जारी प्राप्त करने /खोलने की तिथि को अवकाश घोषित हो जाता है। तो टेंडर अगले कार्य दिवस पर निश्चित समय पर प्राप्त किए/खोले जाएंगे। ज्यादा जानकारी व संशोधित कंटेन्टस ऑफ वर्क्स हेतु बीबीएमबी वेबसाईट www.bbmb.gov.in पर login करें।

(ई.रविन्द्र श्योकन्द)
अति अधीक्षण अभियंता
400 केवी/ टीएल मण्डल,
बीबीएमबी, धूलकोट