

PROFORMA FOR SUPPLYING NIT INFORMATION

Tendering Authority	Addl Superintending Engineer, O&M Division BBMB Dhulkote, Ambala City-134007, Haryana
Scope of Work	Repair & Replacement work at 220 KV sub-station, BBMB Dhulkote(Ambala City)
Tender reference No.	NIT No. 02 , O&M Division BBMB Dhulkote dated 20.06.2018
Last date of issue of Tender Documents	19.07.2018 Upto 17:00 Hrs
Due date/ Time for submission of Tenders	20.07.2018 Upto 13:00 Hrs
Date/ Time of opening of Tenders	20.07.2018 At 15:30 Hrs
Tender Fee	Rs.1180/- (Inclusive of GST) (Non-Refundable)
Earnest Money Deposit	Rs.7100/-
Address for communication	Addl Superintending Engineer, O&M Division BBMB Dhulkote, Ambala City-134007, Haryana
NIT Details	Attached
Date of posting on the Website	
Date of removal from the Website	
Category	Civil work

(Er. Narendra Sharma)
Addl Superintending Engineer
O&M Division, BBMB Dhulkote,
Ambala City.

BHAKRA BEAS MANAGEMENT BOARD

NOTICE INVITING TENDERS

NIT No. 02 dated 20.06.2018	
Name of Office :	Addl Superintending Engineer, O&M Division BBMB Dhulkote, Ambala City-134007, Haryana
Name of Work	Repair & Replacement work at 220 KV sub-station, BBMB Dhulkote(Ambala City)
Last date of issue of Tender Documents	19.07.2018 Upto 1700 Hrs
Website for details	The detailed NIT may be downloaded from BBMB official Website www.bbmb.gov.in
Total cost of the work	Rs. 7.06 Lacs
Earnest Money to be Deposited	Rs-7100/-

(Er. Narendra Sharma)
Addl Superintending Engineer
O&M Division, BBMB Dhulkote,
Ambala City.

BHAKRA BEAS MANAGEMENT BOARD (PW)

NIT No. 02 , O&M Division BBMB Dhulkote

Dated: 20.06.2018

Sealed Tenders are hereby invited on behalf of BBMB for the execution of the following work from reputed civil contractors on item rate:

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Validity	Completion Period	Date of Opening of Tenders
01	Repair & Replacement work at 220 KV sub-station, BBMB Dhulkote(Ambala City)	7.06 Lac	7100/-	90-days	3-months	20.07.2018 at 15:30 Hrs

1. Tender documents can be purchased against cash payment of Rs.1180/- (Inclusive of GST) (Rs. One Thousand One Hundred Eighty Only) (Non-Refundable) from the office of undersigned on any working day between 09:00 AM to 05:00 PM upto 19.07.2018 by Demand Draft in favour of Accounts Officer (Payments) BBMB Dhulkote Ambala City payable on any scheduled bank at Ambala. Documents can also be downloaded from BBMB website www.bbmb.gov.in. The tenders of only those tenderers/ contractors will be accepted/ entertained, who will purchase the tender documents well in advance.
2. Request for issuance of tender forms must accompany copy of pan card & documentary evidence as below:-
 - i) Experience:-
 - a) Average Annual financial turnover during the last 3 years, ending 31st March of the previous financial year, should be at least 30% of the estimated cost (i.e Rs. 7.06 Lacs)
 - b) Experience of having successfully completed similar works during last 7 years ending last day of month previous to the one in which bids are invited should be either of the following:-
 - i) Three similar completed works costing not less than the amount equal to 40% of the estimated cost (i.e Rs. 7.06 Lacs)
 - or
 - ii) Two similar completed works costing not less than the amount equal to 50% of the estimated cost(i.e Rs. 7.06 Lacs)
 - or
 - iii) One similar completed work costing not less than the amount equal to 80% of the estimated cost. (i.e Rs. 7.06 Lacs)
3. Complete tender will be received up to 01:00 PM on the date of opening as mentioned above and will be opened on same day i.e. 20.07.2018 at 03:30 PM in the office of the undersigned in the presence of contractors/ tenderer's or their authorized representatives, who may wish to be present.
4. In case due date for the receipt/ opening of the tenders happens to be a holiday, the tenders will be received/ opened on the next working day.
5. The department reserves the right to reject any or all tender(s) without assigning any reasons.

(Er. Narendra Sharma)
Addl Superintending Engineer
O&M Division, BBMB Dhulkote,
Ambala City.

एन. आई. टी. का प्रोफॉर्मा

टेंडर जारी करने वाला प्राधिकारी	अति.अधीक्षण अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट अम्बाला शहर – 134007-हरियाणा
टेंडर का क्षेत्र	220 केवी सब स्टेशन बीबीएमबी धूलकोट पर मुरम्मत व प्रतिस्थापन का कार्य करवाने हेतु।
टेंडर क्रमांक	खुली निविदा न.02 दिनांक 20.06.2018
टेंडर जारी करने की अंतिम तिथि	19.07.2018 सांय 5 बजे तक
टेंडर देने की निश्चित तिथि व समय	20.07.2018 दोपहर 1 बजे तक
टेंडर देने की खुलने की तिथि व समय:	20.07.2018 दोपहर 3.30 बजे
टेंडर फीस	रु 1180/- मात्र (GST सहित) (Non-Refundable)
धरोहर राशी	रु 7100/-
पत्राचार का पता	अति.अधीक्षण अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट, अम्बाला शहर – 134007-हरियाणा
निविदा विवरण	संलग्न
वेबसाईट पर जाने की तिथि	
वेबसाईट से हटाए जाने की तिथि	
श्रेणी	सिविल कार्य

(ई.नरेन्द्र शर्मा)

अति अधीक्षण अभियंता

ओ एंड एम मण्डल, बीबीएमबी

धूलकोट,अम्बाला शहर

भाखडा ब्यास प्रबंध बोर्ड

निविदा न. 02 दिनांक 20.06.2018	
कार्यालय का नाम	अति.अधीक्षण अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट, अम्बाला शहर – 134007-हरियाणा
कार्य का नाम	220 केवी सब स्टेशन बीबीएमबी धूलकोट पर मुरम्मत व प्रतिस्थापन का कार्य करवाने हेतु।
टेंडर जारी करने की अंतिम तिथि	19.07.2018 सांय 5:00 बजे तक
विवरण के लिए वेब साईट	विस्तृत निविदा आमंत्रण सूचना बीबीएमबी की अधिकारिक वेबसाईट www.bbmb.gov.in से डाऊनलोड की जा सकती है।
कार्य का अनुमानित व्यय	रू 7.06 लाख
धरोहर राशि जो जमा करवानी है	रू 7100/-

(ई.नरेन्द्र शर्मा)

अति अधीक्षण अभियंता
ओ एंड एम मण्डल, बीबीएमबी
धूलकोट,अम्बाला शहर

भाखडा ब्यास प्रबंध बोर्ड

खुली निविदा क्रमांक संख्या : 02

दिनांक : 20.062018

अति.अधीक्षण अभियंता, ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट अम्बाला शहर -134007- हरियाणा द्वारा मोहरबंद निविदाएं सिविल ठेकेदारों से निविदाएं खुलने की तिथि तक सभी संशोधनों को ध्यान में रखते हुए आईटम रेट के आधार पर निम्नलिखित कार्य के लिए आमंत्रित की जाती हैं :

कार्य का विवरण	अनुमानित राशि (रु)	धरोहर राशि	मान्यता	पूर्ण अवधि	खोलने की तिथि
220 केवी सब स्टेशन बीबीएमबी धूलकोट पर मुरम्मत व प्रतिस्थापन का कार्य करवाने हेतु।	रु 7.06 लाख	रु 7100/-	90-दिन	3-माह	20.07.2018 15:30 बजे

1. निविदा प्रलेख व.कार्यकारी अभियंता, ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट अम्बाला शहर - 134007- हरियाणा के कार्यालय से किसी भी कार्य दिवस में दिनांक 19.07.2018 तक (9:00 AM to 5:00PM) 1180/- inclusive of GST (Rs. One Thousand One Hundred Eighty Only Non-Refundable) का डिमांड ड्राफ्ट द्वारा जोकि Accounts Officer BBMB Dhulkote (Ambala City) के पक्ष में हो तथा अंबाला शहर स्थित किसी भी scheduled bank में payable हो, जमा कर प्राप्त किया जा सकता है। यह दस्तावेज बीबीएमबी की वेबसाईट www.bbmb.gov.in से भी ले सकते हैं।

2. Request for issuance of tender forms must accompany copy of pan card & documentary evidence as below:-

i) Experience:-

a) Average Annual financial turnover during the last 3 years, ending 31st March of the previous financial year, should be at least 30% of the estimated cost(i.e Rs. 7.06 Lacs)

b) Experience of having successfully completed similar works during last 7 years ending last day of month previous to the one in which bids are invited should be either of the following:-

i) Three similar completed works costing not less than the amount equal to 40% of estimated cost (i.e Rs. 7.06 Lacs)

or

ii) Two similar completed works costing not less than the amount equal to 50% of the estimated cost (i.e Rs. 7.06 Lacs)

or

iii) One similar completed work costing not less than the amount equal to 80% of the estimated cost. (i.e Rs. 7.06 Lacs)

3. निविदा दिनांक 20.07.2018, 13:00 बजे तक अति अधीक्षण अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट अम्बाला शहर-134007- हरियाणा) के कार्यालय में पहुंचनी चाहिए। निविदा दिनांक 20.07.2018 को 15:30 बजे ठेकेदारों या उनके प्राधिकृत प्रतिनिधियों के समक्ष खोली जाएंगी।

4. यदि इस दिन अवकाश हो जाता है तो निविदाएं अगले दिन उसी समयानुसार प्राप्त/ खोली जाएंगी।

5. विभाग को बिना कोई कारण बताए निविदाएं रद्द करने का अधिकार है।

(ई.नरेन्द्र शर्मा)

अति अधीक्षण अभियंता

ओ एंड एम मण्डल, बीबीएमबी

धूलकोट,अम्बाला शहर



कार्यालय : अति अधीक्षण अभियंता, ओ एण्ड एम मण्डल, धूलकोट (अम्बाला शहर) -13400
Office of : Addl Superintending Engineer, O&M Division, Dhulkote (Ambala City)
Telefax : 0171-2540355, Email : xenomdkt@bbmb.nic.in



सेवा में,

संयुक्त निदेशक, जन सम्पर्क,
सैक्टर-19 बी, मध्य मार्ग, बीबीएमबी चण्डीगढ़ ।

क्रमांक :

दिनांक :

विषय:- निविदा आमंत्रण सूचना संख्या 02/2018-19/O&M DKT दिनांक 20.06.2018, ओ एंड एम मण्डल बीबीएमबी धूलकोट (अम्बाला) के प्रकाशन हेतु ।

विषय संबंधित निविदा आमंत्रण सूचना की दो प्रतियाँ हिन्दी व अंग्रेजी में निम्नलिखित समाचार पत्रों में प्रकाशन हेतु भेजी जाती है जी :

क्रमांक सं	समाचार पत्र का नाम	प्रकाशित होने वाले क्षेत्र का नाम	भाषा
01	Hindustan Times	Chandigarh	English
02	The Indian Express	Chandigarh	English
03	पंजाब केसरी	चण्डीगढ़/ अम्बाला	हिन्दी
04	दैनिक भास्कर	पानीपत/ अम्बाला	हिन्दी

उपरोक्त आपको अति शीघ्र कार्यवाही हेतु प्रेषित है जी तथा इस कार्य पर होने वाला व्यय ओ एंड एम मण्डल बीबीएमबी धूलकोट (अम्बाला) के कार्यालय के आक्समिक खर्च को प्रभारित होगा ।

संलग्न/ उपरोक्तानुसार

(ई.नरेन्द्र शर्मा)

अति अधीक्षण अभियंता
ओ एंड एम मण्डल, बीबीएमबी
धूलकोट, अम्बाला शहर

प्रतिलिपि : 1. मुख्य अभियंता/ पारेषण प्रणाली बीबीएमबी चण्डीगढ़ ।
2. उप मुख्य अभियंता/ ओ एंड एम सर्कल बीबीएमबी जमालपुर ।
3. EDP मैनेजर, Computer Cell बीबीएमबी चण्डीगढ़ को e-mail द्वारा इस अनुरोध के साथ कि विषय चर्चित निविदा आमंत्रण सूचना को BBMB Website www.bbmb.gov.in पर डाला जाए ।

Content of work

S.No.	Description	Qty	Item rate inclusive of GST
1	Removing Doors and Windows (Steel or wood) with chowkhats by making recesses in walls when the wall is not to be dismantled.(Pb. CSR Ref. No. 8.26 (a,b & c) L/R (a) Doors of area 3 sqm. and below (b) Windows of area 3 sqm. and below (C) Clear storey windows of area 3 sqm and below	12 nos 01 no. 02 no.	
2	Dismantling brick work tile masonry or tile lining (b) in cement(Pb. CSR Ref.-8.5 (b) (L/R)	15.47 cum	
3	Dismantled 9 rows of brabed wire on Y-shapes angel iron and stacking it in rolls & carring to designated place (N.S items)	24.54 mtrs	
4	Dismantling concrete or precast concrete. (e) Reinforced Cement concrete (Pb.CSR Ref.8.6 (e) L/R	6.38 cum	
5	Dismantling concrete or precast concrete (d) Cement concrete plain 1:2:4 (Pb. CSR Ref. No. 8.6 (d) L/R	5.02 cum	
6	Dismantling concrete or pre-cast concrete. Lime concrete, cement concrete 1:6:12 or leaner Pb. CSR Ref.(8.6)(a) L/R	5.02 cum	
7	Cement Concrete 1:8:16 with 40mm gauge stone aggregate Ref. (10.6)(b)(i) T/R	5.02 cum	
8	Scraping (c) cement plaster. (Pb. CSR Ref. No.8.31 (c) (L/R)	621.30 sqm	
9	Cutting chase in brick walls in cement or in floor for embedding GI or CI pipes line and making good the same to its original condition Ref (30.85) L/R New chapter (a) Size 75 mm x 75 mm	18.28 mtr	
10	Centring and shuttering for columns (Square or rectangular or poly gonal in plain) (Pb.CSR Ref.9.4) T/R	0.95 sqm	
11	Centring and shuttering for sides and soffits of beam, beams launchings girders bressumers, lintels. (Pb.CSR Ref.9.6) T/R	0.63 sqm	
12	Centring and shuttering for flat surfaces such as suspended floors, roofs, landings, chajjas, shelves etc. (Pb. CSR Ref. No. 9.8+ Extra for shuttering where any single stroey height exceets 4 meters in height for every additional height of two meters or part there of (expect for item no 9.16))PbCSR Ref.-9.18- T/R	50.00 sqm	
13	Centring and shuttering for flat surfaces such as suspended floors, roofs, landings, chajjas, shelves etc. (Pb. CSR Ref. 9.8) T/R	100.00 sqm	
14	Steel work, fixed independently without connecting plates, including cutting, hoisting and fixing in position (c) Tees, angles and channels. (Pb. CSR Ref- 18.1(c) T/R	0.90 Qtl	
15	Cold twisted deformed (Ribbed/Tor Steel Bar) Bars Fe 500 grade as per IS 1786-2008, for R.C.C works, where not including in the complete rate of RCC including bending and placing in position complete(PbCSR Ref.18.18)T/R A&C Slip	4.20 Qtl	
16	Cement Concrete 1:2:4 with stone ballast or shingle(Pb.CSR Ref.No. 10.12) (i) T/R	5.13 cum	
17	Providing, laying, fixing and jointing of PVC pipes as per ISI 4985 (ISI marked with the prior approval of E.I.C. along the trenches and laying the same in trenches to correct alignment and gradients, cutting, jointing and testing complete as per specifications (v) 160 mm o/d of 10 Kg/sqcm (Pb CSR Ref.28.13 (B) (vi) T/R New Chapter	13.41 mtrs	
18	Reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixture as per IS 1791 & needle vibrator but excluding steel reinforcement centring and shuttering in structure. (PbCSR Ref.10.21) A&C Slip T/R	6.38 cum	
19	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS :15622 (thickness to be specified by the manufacture of approved make in all colours, shades except burgundy, bottle green, black of size 310 x 450 mm as approved by Engineer-in-Charge in skirting,risers of steps and dados over 12 mm thick bed of cement Mortar 1:4 (1 cement: 4coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complet (Pb CSR 14.143) (T/R)	14.63 sqm	

20	Anti-skid floor tiles 10mm thick in flooring skirting and dado in 12.5mm thick cement plaster 1:3 in base and jointed with white cement slurry in joints including corners angles and beading.(Ref.14.71) T/R	48.80 sqm	
21	First class burnt brick work laid in cement sand mortar 1:5 in first storey upto 4 metres above plinth level. (Pb. CSR Ref. 11.6) T/R	21.94 cum	
22	12.5 mm thick cement plaster 1:5 (Pb .CSR Ref. No.15.10) T/R	673.32 sqm	
23	Cement pointing 1:3 deep variety(Pb. CSR Ref. 15.60) T/R	116.12 sqm	
24	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate z sections and other sections conforming to Is:733 and IS : 1285 of Jindal, Hindalco, Mahavir or Equivalent make approved by Engineer in Charge , fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC Plug/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/ paneling, C.P.brass / stainless steels screws, all complete as per architectural drawings and the directions of Engineer-In-Charge. (Glazing and paneling to be paid for separately) (a) For fixed portion and chaukhats (Pb. CSR Ref. 17.45 (a) T/R	119.58 kgs	
25	(b) For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and labour for fixing of fittings wherever required including the cost of PVC Plug / neoprene gasket required (Pb. CSR Ref. No. 17.45 b) T/R	162.84 kgs	
26	Providing polyster powder coating 50 micron any coloured specified to aluminium section of various size including carriage of material from market to workshop (pb. CSR Ref. No. 18.54) A & C Slip (Through Rate)	282.42 kgs	
27	Providing and fixing 12mm thick pre laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-In-Charge. Pre-laminated particle board with decorative lamination on both sides.). CSR Ref. 17.46 (ii) T/R	20.44 sqm	
28	Providing and fixing glazing in aluminium door,window, ventilator shutters and partitions etc.with PVC Plug/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item)(Pb. CSR Ref.17.47 (ii) Float glass panes of 4mm thickness T/R	6.24 sqm	
29	Providing and fixing aluminium sliding door bolts ISI marked anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete : 250mmx16 mm Ref(17.49df (b) T/R	12 nos.	
30	Providing and fixing hydraulic door closers ISI Mark with necessary screws etc complete (b) ISI designation no2 size of door 701 mm to 850 mm (Pb. CSR Ref. 17.43 (b) T/R	08 nos	
31	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metres openable length (total length 90 m) having 50 nos. rounds per 6 metres length upto 3 metres height of wall with existing angle iron Y- shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. Reinforced barbed wire ,studied with G.I. staples and G.I. Clips,to retain horizontal ,including necessary bolts or G.I. Barbed wire tied to angle iron all complete as per direction of E.I.C. with reinforced barbed tape (R.B.T.) /Spring core (2.5 mm)wire of high tensile strength of 165 Kg./sqmm.with tape (0.52 mm thick)and weight 43.478 gm/metre Ref DSR 16.53 (T/R)	24.54 mtrs	
32	Cost of Aluminium fittings complete for doors, windows such as tower bolts, handless and screw etc. for these fittings (Excluding sliding bolt)) Pb. CSR Ref. 17.23) (II)For shutter area above 0.50 sqm. - T/R	23.41 sqm	

33	PVC HDPE PIPES & PVC FLEXIBLE PIPES Supply & erection of PVC pipes & HDPE pipes (fire retardant) for wiring purposes including bends, inspection boxes etc where necessary including other petty material as per PWD General specification 2010. (VII) Heavy gauge PVC conduit pipe 25mm dia 2mm thick (ISI make) flushed. Ref. No.33.12 (vii) T/R-	15.24 mtrs	
34	Loading & unloading charges: Stone (building or pitching). Sand, Earth, Fly Ash, Bajri, Shingle Spalls, Brick bats, Brick ballast and stone metal, by manual means within 15 mtrs lead. (Ref.4.1 (B) L/R	29.07 cum	
35	Carriage of Malba Distance 15 KMs: Earth, surkhi, sand, earth, fly ash, bajri, ballast, stone boulders, kankar and building rubbish earth upto 15.00 Km (Pb CSR Ref.5.2 (i)L/R	29.07 cum	
36	Scraping - White wash and colour wash. (Ref.8.31 (a) (L/R)	769.10 sqm	
37	Finishing walls with exterior decorative cement based such as snowcem, robbiacem etc. on old work one coat to give an even shade. (Pb CSR Ref.16.15) T/R	878.68 sqm	
38	Distemping with Acrylic washable oil bound distemper (of approved manufacture) two coats on old distemped work. (Pb. CSR Ref. 16.13) T/R	677.70 sqm	
39	Preparation of plastered or concrete surface for painting (including sand papering the surface) using ready mixed cement based wall putty by applying two coats to get required finish. Ref(16.66) T/R	271.18 sqm	
40	White washing (two coat) (Pb. CSR Ref. 16.2) T/R	366.34 sqm	
41	Providing & laying in superstructure for first storey factory made with vipro-hydraulic compaction machine precast hollow block of cement concrete setting in position with cement mortar 1:3 (1 cement 3 coarse sand) including cost of hoisting, centering and shuttering complete as per IS:2185 (part-1) 2005 (pb. CSR Ref.No,11.75) T/R A & C Slip	14.20 cum	

Remarks- Cost of 7000 no. old and used bricks will be reduced from the bill of contractor.

(नरेन्द्र शर्मा.ई)
अति अधीक्षण अभियंता
ओ एंड एम मण्डल, बीबीएमबी
धूलकोट, अम्बाला शहर