



भाखड़ा ब्यास प्रबन्धक बोर्ड

कार्यालय: वरिष्ठ कार्यकारी अभियंता
ओ एण्ड एम मण्डल, बीबीएमबी, जालन्धर-144006
टैली.फैक्स न: 0181-2414559

पत्र क्रमांक: _____ / EN-911
सेवा में

दिनांक:

उप निदेशक, (जन समपक)
पलाट न. 6-बी, मध्य मार्ग, सैक्टर 19-बी,
बीबीएमबी चण्डीगढ़।

विषय: N.I.T. No. 03/2016-17, dated 15.11.2016 due for open on 5.12.2016 for civil work for providing Nitrogen injection fire prevention and extinguisher system on 220KV/66KV 60MVA Transformer T-3 (Make NGEF) and 220KV/66KV, 100MVA transformer T-4 (Make BHEL) at 220KV Sub Station BBMB Sangrur – Corrigendum-I.

संदर्भ: इस कार्यालय का पत्र क्रमांक: 5292-97 दिनांक: 15.11.16.

In this regard it is intimated that the subject cited N.I.T was published in the following Newspapers:-

1. The Times of India, Chandigarh (English)
2. Dainik Bhaskar, Jalandhar (Hindi).
3. Punjab kesri Jalandhar (Hindi).
4. The Ajit, Jalandhar (Punjabi).

The last date & time of issue of tenders was 2.12.16 up to 5.00PM & the date of opening of tenders 5.12.16 at 3.30 PM. But no contractor/firm has purchased the tender documents from this office up to 5.00PM of 2.12.16.

It is therefore requested that a corrigendum & detail of work (Copies enclosed) may be got published in the concerned newspapers for extension of date of issue, receipt & opening of the tenders as under:-

- 1) Last date of issue of tender documents 15.12.16 up to 5.00 PM.
- 2) Last date of receipt of tender 16.12.16 up to 1.00 PM.
- 3) Date & time of opening of tender 16.12.16 at 3.30 PM.

संलग्न/- उपरोक्त अनुसार

वरिष्ठ कार्यकारी अभियंता,
ओ एण्ड एम मण्डल, बीबीएमबी,

जालन्धर

Endst No.

Dated

The copy of the above is forwarded to the following for information and necessary action, in continuation to this office Memo No 5292-97 dated 15.11.16.

- 1) CE/TS BBMB Chandigarh
- 2) Dy. CE O&M Circle BBMB Jamalpur (Ldh)
- 3) The EDP Manager, BBMB, SLDC Complex Chandigarh9 (through e-mail) for uploading the the aforesaid corrigendum & detail of work on BBMB Website www.bbmb.gov.in
- 4) Er Mukesh Verma AD Civil o/o Director P&D (TS), BBMB Chandigarh.
- 5) SDO T/L BBMB Jalandhar.

वरिष्ठ कार्यकारी अभियंता,
ओ एण्ड एम मण्डल, बीबीएमबी, जालन्धर

BHAKRA BEAS MANAGEMENT BOARD (POWER WING)

CORRIGENDUM - I

N.I.T. No 03/2016-17

DATED 15.11.16

It is hereby informed that the opening date of aforesaid N.I.T. for civil work for providing Nitrogen injection fire prevention and extinguisher system on 220KV/66KV 60MVA Transformer T-3 (Make NGEF) and 220KV/66KV, 100MVA transformer T-4 (Make BHEL) at 220KV Sub Station BBMB Sangrur is extended as here under:-

1. Last date for issue of Tender documents:- 15.12.2016 up to 17.00 Hrs
2. Date and time of submission of Tenders:- 16.12.2016 up to 13.00 Hrs.
3. Date and time for opening of Tenders:- 16.12.2016 at 15.30 hrs

All other terms and conditions of above noted NIT shall however remain unchanged.

For more details log on to **BBMB Website www.bbmb.gov.in**

Sr XENO&M Division
BBMB, Jalandhar

भाखडा ब्यास प्रबन्धक बोर्ड (पी. डब्ल्यू)

शुद्धि पत्र -I

निविदा सूचना न : 3/ 2016-17

निविदा सूचना स. 3/2016-17 दिनांक 15.11.2016 जो कि सिवल कार्य, नाईटरोजन इंजेक्शन आग से बचाव और बुझाने की प्रणाली को 220/66 केवी 60एमवीए टी-3 ट्रांसफारमर (मेक एनजीईएफ) और 220/66 केवी 100एमवीए टी-4 ट्रांसफारमर (मेक बीएचईएल) 220केवी सब स्टेशन बीबीएमबी संगरूर पर स्थापित करने के लिए दिनांक 5.12.2016 को देय था, कि तिथि निम्नलिखित अनुसार बढ़ाई जाती है:-

1. टेंडर जारी करने कि अंतिम तिथि : 15.12.2016 (सुबह 9:00 बजे से सायं 5:00 बजे तक)
2. टेंडर देने की नियत तिथि व समय : 16.12.2016 (दोपहर 1:00 बजे तक)
3. टेंडर खुलने की तिथि व समय : 16.12.2016 (दोपहर 3:30 बजे तक)

निविदा की अन्य शर्तें पूर्वोत्तर ही रहेगी ।

अधिक जानकारी के लिए भाखडा ब्यास प्रबन्धक बोर्ड के वेब साईट www.bbnb.gov.ni.c पर लॉग-आन करे ।

वरिष्ठ कार्यकारी अभियंता,
ओ एण्ड एम मण्डल,
बीबीएमबी, जालन्धर
दूरभाष/टैली.फैक्स न: 0181-2414559

Detail of civil work for providing Nitrogen injection Fire prevention and Extinguisher System on 220KV/66 KV 60 MVA Transformer T-3 (Make NGEF) and 220KV/66 KV, 100 MVA transformer T-4 (Make BHEL) at 220 KV S/Stn.BBMB Sangrur

Sr No	Description	CSR Ref	Unit	Qty
1	Earth work in excavation in foundations, trenches etc. in all kinds of soil where pick jumper work is not involved and not exceeding 2.0 metres depth including dressing of bottom and sides of trenches, stacking the excavated soil clear from the edge of excavation.	6.6	Cum	96.32
2	Cement concrete 1:6:12 with brick ballast 40mm gauge.	10.7(a)	Cum	2.68
3	Reinforced cement concrete M-25 with cement @425/kg per cum hand mixed but excluding steel reinforcement centring and shuttering in superstructure.	10.22	Cum	5
4	First class burnt brick work laid in cement sand mortar 1:6 in first storey upto 4 metres above plinth level	11.4	Cum	25.50
5	Earth filling under floors with surplus ordinary soil or soil containing gravel or kankar upto 40% excavated from foundation and taken only from outside the building plinth in 15 cm layers including ramming, watering and consolidating lead upto 30 metres	6.8(a)(i)	Cum	43.40
6	Structural steel work in angles, tees and flats, riveted or welded including cutting fixing all gusset plates, bolts, nuts, rivets, welding rod etc. with hoisting and erecting in position:- For roof trusses, well curbs, plates and trussed girders, etc. of any span for buildings and bridges up to 15 m span.	18.3(a)	Qtl.	22.99
7	20mm thick cement plaster 1:4 in two coat work	15.20	Sqm	72.14
8	Hoisting arrangement as per site requirement for completion of the work.	Non Schedule item	Job	2

.....2.....

9	Reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixture as per IS 1791 and vibrated by middle vibrator but excluding steel enforcement centering and shuttering in foundation and plinth.	10.15	Cum	1.00
10	Cold twisted deformed (Ribbed/ Tor Steel Bar) Bars Fe 500 grade as per IS 1786-1985, for R.C.C works, where not including in the complete rate of RCC including bending and placing in position complete	18.18	Qtl.	5.50
11	Sealing compound for joint filling	Non Schedule item	Job	2
12	Extra for providing and mixing water proofing material (Liquid or powder) in cement plaster work as per manufacturer guideline and to the entire satisfaction of Engineer-in-charge.	15.47	Cement bag	97.04

(Er.Navdeep Kumar Kamboj)
Sr.Xen/O&M Division
BBMB Jalandhar