

PROFORMA FOR SUPPLYING NIT INFORMATION

Tendering Authority	Sr Executive Engineer, O&M Division BBMB Dhulkote, Ambala City-134007, Haryana
Scope of Work	Modification of existing 02 no. transformer's foundations and construction of new auxiliary foundations, trenches for control cables etc. at 220 KV S/S, BBMB, Dhulkote (Ambala City)
Tender reference No.	NIT No.10 dated 09.12.2016
Last date of issue of Tender Documents	19.12.2016 Upto 15-30 Hrs
Due date/ Time for submission of Tenders	20.12.2016 Upto 13-00 Hrs
Date/ Time of opening of Tenders	20.12.2016 At 15-30 Hrs
Tender Fee	Rs.1000/- (Non-Refundable)
Earnest Money Deposit	Rs.9800/-
Address for communication	Sr Executive Engineer, O&M Division BBMB Dhulkote, Ambala City-134007, Haryana
NIT Details	Attached
Date of posting on the Website	
Date of removal from the Website	
Category	Civil work

(Er. Ravinder Sheokand)
Sr Executive Engineer
O&M Division, BBMB Dhulkote,
Ambala City.

BHAKRA BEAS MANAGEMENT BOARD

NOTICE INVITING TENDERS

NIT No. 10 dated 09.12.2016	
Name of Office :	Sr Executive Engineer, O&M Division BBMB Dhulkote, Ambala City-134007, Haryana
Name of Work	Modification of existing 02 no. transformer's foundations and construction of new auxiliary foundations, trenches for control cables etc. at 220 KV S/S, BBMB, Dhulkote (Ambala City)
Last date of issue of Tender Documents	19.12.2016 Upto 15:30 Hrs
Website for details	The detailed NIT may be downloaded from BBMB official Website www.bbmb.gov.in
Total cost of the work	Rs. 9.80 Lacs
Earnest Money to be Deposited	Rs. 9800/-

(Er. Ravinder Sheokand)
Sr Executive Engineer
O&M Division, BBMB
Dhulkote, Ambala City.

BHAKRA BEAS MANAGEMENT BOARD (PW)

NIT No. 10

Dated: 09.12.2016

Sealed Tenders are hereby invited on behalf of BBMB for the execution of the following work from reputed civil contractors on item rate:

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Validity	Completion Period	Date of Opening of Tenders
01	Modification of existing 02 no. transformer's foundations and construction of new auxiliary foundations, trenches for control cables etc. at 220 KV S/S, BBMB, Dhulkote (Ambala City)	9.80 Lacs.	9800/-	90-days	3-months	20.12.2016 at 15:30 Hrs

1. Tender documents can be purchased against cash payment of Rs.1000/- (Rs.One Thousand Only) (Non-Refundable) from the office of undersigned on any working day between 09:00 AM to 03:30 PM upto 19.12.2016 by cash or by Demand Draft in favour of Accounts Officer (Payments) BBMB Dhulkote Ambala City payable on any scheduled bank at Ambala. Documents can also be downloaded from BBMB website www.bbmb.gov.in. The tenders of only those tenderers/ contractors will be accepted/ entertained, who will purchase the tender documents well in advance.
2. Request for issuance of tender forms must accompany copy of pan card & documentary evidence as below:-
Tenderer must have successfully completed the civil works up to tender value in last three years.
3. Complete tender will be received up to 01:00 PM on the date of opening as mentioned above and will be opened on same day i.e. 20.12.2016 at 03:30 PM in the office of the undersigned in the presence of contractors/ tenderer's or their authorized representatives, who may wish to be present.
4. In case due date for the receipt/ opening of the tenders happens to be a holiday, the tenders will be received/ opened on the next working day.
5. The department reserves the right to reject any or all tender(s) without assigning any reasons.

(Er. Ravinder Sheokand)
Sr Executive Engineer
O&M Division, BBMB
Dhulkote, Ambala City.

एन. आई. टी. का प्रोफॉर्मा

टेंडर जारी करने वाला प्राधिकारी	व.कार्यकारी अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट अम्बाला शहर – 134007-हरियाणा
टेंडर का क्षेत्र	220 के वी सब स्टेशन बीबीएमबी धूलकोट अंबाला शहर स्थित existing 02 न. ट्रांसफोर्मर की फ़ाउंडेशन की modification तथा नई auxiliary फ़ाउंडेशनें, तथा control cables की trenches बनाने के लिए।
टेंडर क्रमांक	निविदा न.10 दिनांक 09.12.2016
टेंडर जारी करने की अंतिम तिथि	19.12.2016 सांय 3:30 बजे तक
टेंडर देने की निश्चित तिथि व समय	20.12.2016 दोपहर 1 बजे तक
टेंडर देने की खुलने की तिथि व समय:	20.12.2016 दोपहर 3.30 बजे
टेंडर फीस	रु 1000/- मात्र (Non-Refundable)
धरोहर राशी	रु 9800/-
पत्राचार का पता	व.कार्यकारी अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट, अम्बाला शहर – 134007-हरियाणा
निविदा विवरण	संलग्न
वेबसाईट पर जाने की तिथि	
वेबसाईट से हटाए जाने की तिथि	
श्रेणी	सिविल कार्य

(ई.रविन्द्र श्योकन्द)

व.कार्यकारी अभियंता

ओ एंड एम मण्डल, बीबीएमबी

धूलकोट,अम्बाला शहर ।

भाखडा व्यास प्रबंध बोर्ड

निविदा न. 10 दिनांक 09.12.2016	
कार्यालय का नाम	व.कार्यकारी अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट, अम्बाला शहर - 134007-हरियाणा
कार्य का नाम	220 के वी सब स्टेशन बीबीएमबी धूलकोट अंबाला शहर स्थित existing 02 न. ट्रांसफोर्मर की फ़ाउंडेशन की modification तथा नई auxiliary फ़ाउंडेशनें, तथा control cables की trenches बनाने के लिए।
टेंडर जारी करने की अंतिम तिथि	19.12.2016 सांय 3:30 बजे तक
विवरण के लिए वेब साईट	विस्तृत निविदा आमंत्रण सूचना बीबीएमबी की अधिकारिक वेबसाईट www.bbmb.gov.in से डाऊनलोड की जा सकती है ।
कार्य का अनुमानित व्यय	रू 9.80 लाख
धरोहर राशि जो जमा करवानी है	रू 9800/-

(ई.रविन्द्र श्योकन्द)

व.कार्यकारी अभियंता

ओ एण्ड एम मण्डल, बीबीएमबी

धूलकोट,अम्बाला शहर ।

भाखडा ब्यास प्रबंध बोर्ड

प्रेस निविदा क्रमांक संख्या : 10

दिनांक : 09.12.2016

व.कार्यकारी अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट अम्बाला शहर -134007- हरियाणा द्वारा मोहरबंद निविदाएं सिविल ठेकेदारों से निविदाएं खुलने की तिथि तक सभी संशोधनों को ध्यान में रखते हुए आईटम रेट के आधार पर निम्नलिखित कार्य के लिए आमंत्रित की जाती हैं :

कार्य का विवरण	अनुमानित राशि (रु)	धरोहर राशि	मान्यता	पूर्ण अवधि	खोलने की तिथि
220 के वी सब स्टेशन बीबीएमबी धूलकोट अंबाला शहर स्थित existing 02 न. ट्रांसफोर्मर की फ़ाउंडेशन की modification तथा नई auxiliary फ़ाउंडेशनें, तथा control cables की trenches बनाने के लिए।	रु 9.80 लाख	रु 9800/-	90-दिन	3-माह	20.12.2016 15:30 बजे


1. निविदा प्रलेख व.कार्यकारी अभियंता, ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट अम्बाला शहर - 134007- हरियाणा के कार्यालय से किसी भी कार्य दिवस में दिनांक **19.12.2016** तक (9:00 AM to 3:30) 1000/- (Rs. One Thousand Only Non-Refundable) का नकद भुगतान करके या डिमांड ड्राफ्ट द्वारा जोकि Accounts Officer BBMB Dhul kote (Ambala City) के पक्ष में हो तथा अंबाला शहर स्थित किसी भी scheduled bank में payable हो, भेज कर प्राप्त किया जा सकता है। यह दस्तावेज बीबीएमबी की वेबसाईट www.bbnb.gov.in से भी ले सकते हैं।
2. निविदा प्रलेख प्राप्त करने हेतू प्रार्थना पत्र के साथ ठेकेदार को PAN Card की प्रतिलिपि व निम्नलिखित documentary evidence संलग्न होने चाहिए :-
ठेकेदार द्वारा पिछले 3-साल में tendered value की राशि तक के सिविल कार्य सफलता पूर्वक पूर्ण किए होने चाहिए।
3. निविदा दिनांक 20.12.2016, 13:00 बजे तक व.कार्यकारी अभियंता,ओ एण्ड एम मंडळ, बीबीएमबी धूलकोट अम्बाला शहर-134007- हरियाणा) के कार्यालय में पहुंचनी चाहिए। निविदा दिनांक 20.12.2016 को 15:30 बजे ठेकेदारों या उनके प्राधिकृत प्रतिनिधियों के समक्ष खोली जाएंगी।
4. यदि इस दिन अवकाश हो जाता है तो निविदाएं अगले दिन उसी समयानुसार प्राप्त/ खोली जाएंगी।
5. विभाग को बिना कोई कारण बताए निविदाएं रद्द करने का अधिकार है।

(ई.रविन्द्र श्योकन्द)

व.कार्यकारी अभियंता

ओ एंड एम मण्डल, बीबीएमबी

धूलकोट, अम्बाला शहर।



भाखड़ा व्यास प्रबन्ध बोर्ड (विद्युत खण्ड)
आई.एस./आई.एस.ओ. 9001, 14001 प्रमाणित बोर्ड
(सांविधिक निकाय, ऊर्जा मंत्रालय, भारत सरकार)



भाखड़ा व्यास
राष्ट्र गौरव

कार्यालय : व.कार्यकारी अभियंता, ओ एण्ड एम मण्डल, धूलकोट (अम्बाला शहर) -134007
Office of : Sr.Executive Engineer, O&M Division, Dhulkote (Ambala City)
Telefax : 0171-2540355, Email : xenomdkt@bbmb.nic.in

सेवा में,

संयुक्त निदेशक, जन सम्पर्क,
सैक्टर-19 बी, मध्य मार्ग, बीबीएमबी चण्डीगढ़ ।

क्रमांक :

दिनांक :

विषय:- निविदा आमंत्रण सूचना संख्या 10 ओ एंड एम मण्डल बीबीएमबी धूलकोट (अम्बाला)
दिनांक 09.12.2016 के प्रकाशन हेतु ।

विषय संबंधित निविदा आमंत्रण सूचना की दो प्रतियाँ हिन्दी व अंग्रेजी में निम्नलिखित

समाचार पत्रों में प्रकाशन हेतु भेजी जाती है जी :

क्रमांक सं	समाचार पत्र का नाम	प्रकाशित होने वाले क्षेत्र का नाम	भाषा
01	Hindustan Times	Chandigarh	English
02	The Indian Express	Chandigarh	English
03	पंजाब केसरी	चण्डीगढ़/ अम्बाला	हिन्दी
04	दैनिक भास्कर	पानीपत/ अम्बाला	हिन्दी

उपरोक्त आपको अति शीघ्र कार्यवाही हेतु प्रेषित है जी तथा इस कार्य पर होने वाला व्यय ओ एंड एम मण्डल बीबीएमबी धूलकोट (अम्बाला) के कार्यालय के आक्समिक खर्च को प्रभारित होगा ।

संलग्न/ उपरोक्तानुसार

(ई.रविन्द्र श्योकन्द)
व.कार्यकारी अभियंता,
ओ एण्ड एम मंडल,
धूलकोट (अम्बाला)

प्रतिलिपि : 1. मुख्य अभियंता/ पारेषण प्रणाली बीबीएमबी चण्डीगढ़ ।
2. उप मुख्य अभियंता/ ओ एंड एम सर्कल बीबीएमबी जमालपुर ।
3. EDP मैनेजर, Computer Cell बीबीएमबी चण्डीगढ़ को e-mail द्वारा इस अनुरोध के साथ कि विषय चर्चित निविदा आमंत्रण सूचना को BBMB Website www.bbmb.gov.in पर डाला जाए ।

Contents of Work

S. No.	Description	Qty.
1	Earth work in excavation in foundations, trenches etc in all kind of soil where pick jumper work is not involved and not exceeding 2.0 meters depth including dressing of bottom and sides of trenches, stacking the excavated soil clear from the edge of excavation and subsequent filling around masonry in 15cm layers with compaction including disposal of all surplus soil as directed within a lead of 30-meters. (Ref. No. 6.6) A&C slip- L/R	198.27 Cum
2	Cement Concrete 1:6:12 with 40mm gauge stone aggregate (CSR ref. 10.7(b) T/R)	22.899m ³
3	Dismantling concrete or precast concrete (e) reinforced cement concrete (CSR ref. 8.6(e) L/R	7.16 Cum
4	Shuttering for faces of concrete foundations and foundation beam and plinth beam (vertical or bettering) (CSR ref. 9.1 (L/R)	129.93 Sqm
5	Cold Twisted deformed (Ribbed/ Tor steel Bar) Bars fee 500 grade as per IS 1786-1985, for R.C.C Works where not including in the complete rate of RCC including bending and placing in position complete. (CSR ref.18.18 (T/R)	22.71 Qtl
6	RCC M-20 mechanically batch mixed using batch type, concrete mixer as per IS 1791 & vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in foundation and plinth (Pb.CSR Ref.10.15) T/R A&C Slip.	41.66 Cum
7	RCC M 15 Mechanically batch mixed using batch type conc. mixer as per IS:1791 & Vibrated by needle vibrator but excluding steel reinforcement ,centring and shuttering in foundation and plinth (Pb. CSR Ref No. 10.14 (A &C Slip) T/R	1.64 cum
8	First class brunt brick work laid in cement sand mortar 1:6 in foundation and plinth.(CSR. Ref. 11.3 (T/R)	42.12 cum
9	Welding by gas or by electric plant including carriage to send from workshop (CSR ref 18.28 T/R).	7200 cm
10	Supply of templates of MS flat 50x6 mm as per approved drawings. (N.S. Item)	8 Nos
11	Setting of Templates in proper alignment, leveling and fixing of foundation bolts (N.S. Item)	56 Nos.
12	Removing of existing gravel from site, stacking and relaying of gravel etc. at site (N.S. Item)	400 sqm
13	Supplying and Laying dry brick ballast CSR ref 10.32 (T/R)	1.53 cum
14	Cement Concrete 1:6:12 with brick ballast 40 mm gauge (CSR ref. 10.7(a) T/R)	4.31 m ³
15.	Centring and shuttering for sides and soffits of beam, beams launchings girders bressumers, lintels. (Pb.CSR Ref.9.6) T/R	30.48 sqm
16	Cement Concrete 1:2:4 with stone ballast or shingle. (Pb. CSR Ref.10.12) T/R	6.50 cum
17	16mm thick cement plaster 1:4 in two coat work. (Pb CSR Ref.15.16) (T/R)	72.12 sqm
18	Structural steel work in angles, tees and flats, riveted or welded including cutting fixing all gusset plates, bolts, nuts, rivets, welding rod, etc. with hoisting and erecting in position for roof trusses well curbs plates and trussed girders etc of any span for buildings and bridges. Up to 15 m span(Pb.CSR Ref.18.3(a) T/R	19.74 Qtl
19	Supply and fixing of anchor bolts 8mm dia 125 mm long threaded on one side with nut (NS item)	240 Nos
20	Hand boring horizontal for crossing railway track by using augar/bocki method including excavation complete in all respect (NS item)	6 mtr
21	Providing, lowering in trenches to correct gradient and alignment, jointing with tyton rubber joint and cutting of RCC/SS pipe having inside HDPE lining ISI marked as per ISI code IS :458-2003 in two trenches for all depths and laying out the same to correct alignment, gradient, levels etc, cutting of concrete beds and joints holes, supporting the pipes and special in correct position in a suitable rigid manner while the same are being jointed and until the surrounding benching, haunches and envelopes are completed. The pipe shall rest on the beds at all joints through their lengths and to ensure this, testing the pipe for leakage and making good the same leakage and all defects to the entire satisfaction of EIC including all cartridges etc complete in all respect. CSR Ref 29.64 (I) T/R- New Chapter. (a) 400mm i/d	6 mtr

(ई.रविन्द्र श्योकन्द)
व.कार्यकारी अभियंता,
ओ एण्ड एम मंडळ,
धूलकोट (अम्बाला)